
This Large Scale Development has been reviewed for general compliance with the City of Tontitown Zoning and Planning Ordinances. Oversight of any regulations does not relieve the Owner of their responsibility to comply with all regulations.

Terry W. Carpenter, P.E. Tontitown City Engineer, December 11, 2017



BATES & ASSOCIATES, INC.

STORAGE OPMENT PL

I SI

CONTITON SE SCALI


T. ARGE


ARKANSAS

ONTITOWN,

PLAN

ANDSCA







PLANT LIST

QTY SYM COMMON NAME/

llex opaca

BB JAPANESE HOLLY
Ilex crenata 'Compacto

40 AH AMERICAN HOLLY

BOTANICAL NAME

ROOTMIN. SIZE

B&B 2.5" CAL.

CONT. 5 GAL.

GENERAL LANDSCAPE NOTES

ALL PLANTING BEDS AND TREE AND SHRUB SAUCERS ARE TO HAVE 4" THICK ORGANIC MULCH EVENLY APPLIED IN PLANTING BED. ALL PROPOSED PLANTING AREAS COVERED BY GRASS SHALL HAVE THE SOD COMPLETELY REMOVED BEFORE PLANTING BEGINS.

PLANTING AREAS ARE TO HAVE THE SOIL AMENDED TO ALLOW FOR PROPER TREE GROWTH AS SPECIFIED BY THE LANDSCAPE ARCHITECT.


HOSE BIB IRRIGATION PER CITY OF TONTITOWN SPECIFICATIONS EVERY 100'.

REQUIRED PLANT MATERIAL WILL BE GUARANTEED FOR 3 YEARS. LANDSCAPING THAT DIES OR IS DAMAGED SHALL BE REPLACED BY THE CURRENT OWNER. IT IS THE OWNER'S RESPONSIBILITY TO PROVIDE A SURETY TO THE CITY OF TONTITOWN FOR ALL REQUIRED LANDSCAPING.

MULCH TO BE 2"-3" AWAY FROM TRUNK.

PLANTED VEGETATION TO MEET OR EXCEED ANSI-Z60.1 STANDARDS.

ALL SHRUBS AND PLANTING BEDS WILL BE CONTAINED WITH 3" OR 4" METAL EDGING.



SHRUB PLANTING LEGEND

SYMBOL DESCRIPTION PRUNE BROKEN AND DAMAGED TWIGS AFTER PLANTING


PLACE PLANT IN VERTICAL, PLUMB POSITION REMOVE CONTAINER PRIOR TO PLACING BACKFILL.

3" - 4" OF MULCH PREPARED BACKFILL. TAMP AND SOAK BACKFILL AFTER PLANTING.

PLANTING NOTES

A. AREA OF PREPARED BACKFILL SHALL BE EXCAVATED TO THE WIDTH OF THE PLANTING BED.

shrub planting detail n.t.s.



DECIDUOUS TREE PLANTING LEGEND

SYMBOL DESCRIPTION

1) 4" ORGANIC MULCH. 3"-4" AWAY FROM TRUNK

REMOVE BALL WRAP FROM TOP 1/3 OF BALL

ROOTBALL - ROOT COLLAR SHALL BE VISIBLE; REMOVE EXCESS SOIL FROM TOP OF BALL 1" TO 2" ABOVE FINISHED GRADE TO ALLOW FOR SETTLING.

TREE SAUCER (4" EARTHEN BERM AT EDGE OF DRIP LINE)

EXCAVATE AND REPLACE EXISTING SOIL. ADD SOIL AMENDMENTS AS NECESSARY, AS DIRECTED BY PROJECT MANAGER. WATER THOROUGHLY TO ELIMINATE AIR POCKETS. DO NOT TAMP.

A. RETAIN NATURAL SHAPE. DO NOT SHEAR OR CUT CENTRAL LEADER. TREES WITH CENTRAL LEADERS ARE NOT ACCEPTED IF LEADER IS DAMAGED OR REMOVED.

B. PRUNE DAMAGED TWIGS OR DOUBLE LIMBS AFTER PLANTING ROUGHEN EDGES C. WRAP TREES TO FIRST BRANCH IF PLANTED IN FALL. DO NOT WRAP IF PLANTED IN SPRING.

D. PLACE TREE BALL ON FIRM UNDISTURBED SOIL.

E. REMOVE ANY TWINE, ROPE, FLAGGING, WRAPPING OR GUARDS FROM THE TREE.

tree planting detail n.t.s.

