



201 East Henri de Tonti Blvd.
Post Office Box 305 Tontitown, AR 72770
Phone (479) 361-2700

June 6, 2022

Bashar Qedan P.E.
Arkansas Department of Transportation
3526 N Highway 112
Fayetteville, AR 72704

RE: State Aid Street Project – S Pinalto Road, Tontitown

Mr. Qedan,

As per our phone conversation on 6/6/2022, please accept this letter as a conditional approval to complete the full one and one-half miles of the South Pinalto overlay. I understand that due to amount of damage that has occurred since the original evaluation of the road, it will require an additional \$70,000 to be paid by the City to complete the overlay as planned. I will present this information to the City Council on Tuesday, June 7 for approval. However, if the council does not approve the extra funds, please continue the project for the original amount of the State Aid Street funds of \$300,000, which will allow the overlay to proceed at a shortened distance of one mile.

Thank you,

A handwritten signature in black ink, appearing to read "James Clark". The signature is fluid and cursive, with a long, sweeping underline that extends to the left.

James Clark
Public Works Director

ARKANSAS STATE HIGHWAY COMMISSION CHANGE ORDER

Job Name Tontitown Pinalto Rd. Overlay (S) Route & Section PIANALTO RD.
 Job No. C72012 FAP No 9971C72012 County Washington
 Changes located Pinalto Rd Change Order No. 1

DESCRIPTION OF CHANGE:
 Increase quantity for the item "ACHM Patching of Existing Roadway"

REASON FOR CHANGE:
 Heavy traffic has deteriorated the pavement on S. Pinalto Rd. at various locations. Additional quantities of ACHM Patching of Existing Roadway will be required to restore the pavement section in these deteriorated areas.

Attachments:
 Schedule of Quantities, Letter from City

SUMMARY

Item No.	Item	Unit	Unit Price	PRESENT		REVISED	
				Quantity	Amount	Quantity	Amount
SPSS415	ACHM Patching Of Existing Roadway	TON	304.05	40.00	12,162.00	272.29	82,789.77
					12,162.00		82,789.77
Overrun							<u>\$70,627.77</u>

Concurrence By:

	Date	Initials	Remarks
CONSTRUCTION	_____	_____	_____
STATE AID	_____	_____	_____
CITY MAYOR	_____	_____	_____

Authorized _____

Chad Adams, District Engineer

Requested 6/6/2022

Bashar Qedan

Bashar Qedan, Resident Engineer

Schedule of Quantities

Begin Station	End Station	Width	Location	Area (SF)	Area (SY)	Depth	Tons ACHM
101+55	101+60	21	BT	105	11.67	0.5	2.57
101+60	101+67	4	RT	28	3.11	0.5	0.68
101+55	101+90	4	LT	140	15.56	0.5	3.42
102+60	103+30	4	RT	280	31.11	0.5	6.84
102+60	103+15	4	LT	220	24.44	0.5	5.38
103+40	103+55	4	LT	60	6.67	0.5	1.47
103+64	103+78	4	LT	56	6.22	0.5	1.37
104+50	105+55	5	RT	525	58.33	0.5	12.83
106+90	107+25	4	RT	140	15.56	0.5	3.42
107+90	112+13	4	RT	1692	188	0.5	41.36
110+21	110+46	5	CT	125	13.89	0.5	3.06
110+34	110+38	4	LT	16	1.78	0.5	0.39
110+52	110+76	5	CT	120	13.33	0.5	2.93
110+82	111+37	4	LT	220	24.44	0.5	5.38
111+84	111+95	5	CT	55	6.11	0.5	1.34
112+75	113+51	6	LT	456	50.67	0.5	11.15
112+93	113+30	5	RT	185	20.56	0.5	4.52
113+70	113+79	4	RT	36	4	0.5	0.88
114+04	114+13	5	RT	45	5	0.5	1.1
114+44	114+71	5	RT	135	15	0.5	3.3
114+45	114+68	4	LT	92	10.22	0.5	2.25
114+77	114+81	4	RT	16	1.78	0.5	0.39
115+60	116+80	3	LT	360	40	0.5	8.8
116+80	117+45	3	LT	195	21.67	0.5	4.77
124+95	125+27	3	LT	96	10.67	0.5	2.35
125+70	125+83	6	CT	78	8.67	0.5	1.91
125+93	133+57	4	RT	3056	339.56	0.5	74.7
128+94	130+29	3	LT	405	45	0.5	9.9
144+80	145+38	5	LT	290	32.22	0.5	7.09
154+63	155+14	7	CT	357	39.67	0.5	8.73
157+30	158+45	7	CT	805	89.44	0.5	19.68
160+00	162+00	3	LT	600	66.67	0.5	14.67
168+00	168+40	3	LT	120	13.33	0.5	2.93
175+90	176+00	3	LT	30	3.33	0.5	0.73
Total:							272.29