



**Element Roofing**  
 P.O. Box 11184  
 Fayetteville, AR 72703  
 Phone: 479-521-7663

05/27/2025

**Company Representative**  
 Dylan Ceola  
 Phone: (479) 530-8834  
 Dylan@elementroofingnwa.com

**Tontitown Museum**  
 251 East Henri De Tonti Boulevard  
 Tontitown, AR 72770  
 (555) 555-5555

**Roofing Section**

	Qty	Unit	Price
Remove existing roof (4 layers)	14.00	SQ	\$1,984.50
Install new 7/16 OSB	48.00	PC	\$2,887.50
Install 26 Gauge H-LOC Metal	14.00	SQ	\$11,812.50
Install Rake Trim	8.00	EA	\$0.00
Install Eave Trim	4.00	EA	\$0.00
Install Side-Wall Flashing	1.00	EA	\$0.00
Install Ridge Vent	18.00	LF	\$0.00
Install Hidden Fasteners	1.00	EA	\$0.00
Install Metal Closures	1.00	EA	\$0.00
			<b>\$16,684.50</b>

**Gutters Section**

	Qty	Unit	Price
Install Seamless Aluminum Gutters 6" (West Only)	79.00	LF	\$532.00
Install 3x4 Downspout	19.00	LF	\$212.64
Install Gutter Wedges	1.00	EA	\$118.00
Remove Old Gutters	1.00	LF	\$177.00
			<b>\$1,039.64</b>

**Siding Section**

	Qty	Unit	Price
Remove and Replace Fascia – Steel Metal	159.00	LF	\$4,283.35
Remove and Replace Window Wrap Large	9.00	PC	\$4,303.36
Remove and Replace Window Wrap Small	2.00	PC	\$359.16
Remove and Replace Door Wrap	1.00	EA	\$629.00
Remove and Replace Corbel Wraps	8.00	PC	\$600.00
Remove and Replace 27 pieces of D4" Straight Lap Siding	27.00	PC	\$2,025.00
Please note color is not exact match due to fading			
Remove and Replace 5/8 J Channel	96.00	LF	\$491.52
Dump Fee	1.00	EA	\$550.00
			<b>\$13,241.39</b>

TOTAL

\$30,965.53

**\*I agree to the price and specifications outlined in this contract and all Terms and Conditions and authorize Element Roofing LLC to do the work specified. Payment will be made as outlined above.\***

\_\_\_\_\_  
Company Authorized Signature

\_\_\_\_\_  
Date

\_\_\_\_\_  
Customer Signature

\_\_\_\_\_  
Date

\_\_\_\_\_  
Customer Signature

\_\_\_\_\_  
Date